

REVISED BID TABULATION 10-10-13

Line #	Item Number	Sec #	Description	Quantity	Unit	Unit Cost	Amount
0001	0000100000-N	800	MOBILIZATION	1	LS		
0002	0000400000-N	801	CONSTRUCTION SURVEYING	1	LS		
0003	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM - BMP SAND FILTER	1	LS		
0004	0043000000-N	226	COMPREHENSIVE GRADING	1	LS		
0005	0036000000-E	225	UNDERCUT EXCAVATION	200	CY		
0006	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	700	SY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	6	TN		
0008	0360000000-E	310	12" RC PIPE CULV III	71	LF		
0009	0366000000-E	310	15" RC PIPE CULV III	163	LF		
0010	0372000000-E	310	18" RC PIPE CULV III	10	LF		
0011	0414000000-E	310	60" RC PIPE CULV III	107	LF		
0012	0453000000-E	310	18" PIPE END SECTION	1	EA		
0013	1489000000-E	610	ASP CONC BASE CRS B25.0B	1350	TON		
0014	1498000000-E	610	ASP CONC INTR CRS I19.0B	910	TON		
0015	1519000000-E	610	ASP CONC SURF CRS S9.5B	670	TON		
0016	1575000000-E	620	ASP FOR PLANT MIX	145	TON		
0017	2209000000-E	838	ENDWALLS	11.2	CY		
0018	2286000000-N	840	MASNRY DRAINAGE STRUCT	6	EA		
0019	2308000000-E	840	MASNRY DRAINAGE STRUCT	10	LF		
0020	2374000000-N	840	FRAME-GRT-HD 840.03**	6	EA		
0021	2549000000-E	846	2'-6" CONC CURB & GUTTER	2265	LF		
0022	3628000000-E	876	RIP RAP, CLASS I	25	TON		
0023	3635000000-E	876	RIP RAP, CLASS II	53	TON		
0024	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	170	SY		
0025	3691000000-N	SP	SPECIAL SILT CHECK	13	EA		
0026	4399000000-N	1105	TEMP TRAFFIC CONTROL	1	LS		
0027	4410000000-E	1110	WORK ZONE SIGNS (BARR)	20	SF		
0028	4445000000-E	1145	BARRICADES (TYPE III)	32	LF		
0029	6000000000-E	1605	TEMPORARY SILT FENCE	2995	LF		
0030	6006000000-E	1610	EROS CONTRL STONE CL A	35	TON		
0031	6012000000-E	1610	SEDIMENT CONTROL STONE	10	TON		
0032	6015000000-E	1610	TEMPORARY MULCHING	3.5	ACR		
0033	6018000000-E	1620	SEED FOR TEMP SEEDING	150	LB		
0034	6021000000-E	1622	FERT FOR TEMP SEEDING	0.75	TON		
0035	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF		
0036	6029000000-E	SP	SAFETY FENCE	100	LF		
0037	6030000000-E	1630	SILT EXCAVATION	140	CY		
0038	6036000000-E	1631	MATTING FOR EROS CONTROL	11565	SY		
0039	6037000000-E	SP	COIR FIBER MAT	490	SY		
0040	6042000000-E	1632	1/4" HARDWARE CLOTH	35	LF		
0041	6084000000-E	1660	SEEDING AND MULCHING	2	ACR		
0042	6084000000-E	1660	NATIVE GRASS SEEDING AND MULCHING	0.55	ACR		
0043	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB		
0044	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON		

0045	6096000000-E	1662 SEED FOR SUPP SEEDING	100	LB
0046	6108000000-E	1665 FERTILIZER TOPDRESSING	3	TON
0047	6111000000-E	SP IMPERVIOUS DIKE	170	LF
0048	6117000000-N	SP RESPONSE FOR EROSION CONTROL	7	EA

Total Amount Of Bid For Entire Project: